SHENANDOAH SUBDIVISION, PHASE 8A
Oversize Participation Request for
Decatur Drive and Water Line
November 5, 2003

Item No.	Description	Unit	Quantity	Unit Bid	Total
	47' Paving Construction				
1	Clearing and Grubbing (70 ft ROW)	Acre	1.2	1,000.00	1,200.00
2	Roadway Excavation	C.Y.	2,086	3.25	6,779.50
3	1.5" HMAC Surface Course	S.Y.	3,672	5.00	18,360.00
4	7" Crushed Limestone Base	S.Y.	3,672	7.25	26,622.00
5	6" Lime Stabilized Subgrade	S.Y.	4,172	2.65	11,055.80
				47' Paving Total	$52,961.50
	39' Paving Construction				
1	Clearing and Grubbing (60 ft ROW)	Acre	1.0	1,000.00	1,000.00
2	Roadway Excavation	C.Y.	1,711	3.25	5,560.75
3	1.5" HMAC Surface Course	S.Y.	2,921	5.00	14,605.00
4	7" Crushed Limestone Base	S.Y.	2,921	7.25	21,177.25
5	6" Lime Stabilized Subgrade	S.Y.	3,421	2.65	9,065.65
				39' Paving Total	$42,343.00
				Oversize Participation (Street)	**$10,618.50**
	12" Water System Construction				
1	12" PVC, C900 Water Line, Str. Backfill	L.F.	751	29.50	22,154.50
2	12" Gate Valve	EACH	2	1,100.00	2,200.00
3	12"x 13" Anchor Coupling	EACH	2	264.00	528.00
4	12"x 8" Tee	EACH	1	375.00	375.00
5	12"x 6" Tee	EACH	1	350.00	350.00
				12" Water Total	$25,607.50
	8" Water System Construction				
1	8" PVC, C900 Water Line, Str. Backfill	L.F.	751	21.00	15,771.00
2	8" Gate Valve	EACH	2	530.00	1,060.00
3	8"x 13" Anchor Coupling	EACH	2	100.00	200.00
4	8"x 8" Tee	EACH	1	180.00	180.00
5	8"x 6" Tee	EACH	1	160.00	160.00
				8" Water Total	$17,371.00
				Oversize Participation (Water)	**$8,236.50**

STATE OF TEXAS
KENT M. LAZA
65923
REGISTERED
PROFESSIONAL ENGINEER

Kent Laza
11/5/03

Summary

Oversize Participation (Streets)	10,618.50
Oversize Participation (Water)	8,236.50
Total Oversize Participation	**$18,855.00**